

roadside water harvesting (2)

activityname	ward	photo	panchayath	description	longitude	latitude
Road Side Water Harvesting	Karingal	roadsiderecharging.jpg	Maranalloor	A location specific solution to resolve the continuous flooding of a road was experimented under the project and turned successful. 4 m long, 1.5 meter wide and 2 meter pit was constructed on the side of the road. A gentle slope from both the sides was provided towards this pit enabling the water to flow to this pit. The side of the pit adjacent to the road was plastered so that the water does not percolate beneath the road. A honey comb structure was followed to pave the stones so that the water infiltrates down the soil through the three sides. The pit was covered using slabs. The experiment was successful in overcoming the flooding and also to recharge the wells down the pit. The activity was done in collaboration with Public Works Department. Field studies are conducted to replicate the models in other areas.	77.092581	8.47117